

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-30069-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 16-31S-10E
2310 feet from S Section Line, 1980 feet from E Section Line
Lease Name: WALKER Well #: 1
County: ELK Total Vertical Depth: 2095 feet

Operator License No.: 3359
Op Name: T & R OIL COMPANY, A GENERAL PAR
Address: PO BOX 92
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2090	0	
SURF	8.625	115	0	

\$ 68.09

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2006 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL
Date/Time Plugging Completed: 06/29/2006 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" TUBING INSIDE 4.5" CASING DOWN TO 2000' & PUMPED GEL & 10 SACKS CEMENT WITH HULLS FOR BOTTOM PLUG & GEL SPACER. PULLED 1" OUT & PERFORATED 4.5" CASING @ 500'. RAN 1" BACK IN TO 500' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" & TOPPED-OFF WELL. USED TOTAL OF 65 SACKS CEMENT & 4 SACKS GEL.

Perfs:

RECEIVED
KCC DISTRICT

AUG 8 2006 RR

CHANUTE, KS

INVOICE
DATE 10/5/06
WELL NO. 2007060636

Remarks: PLUGGED DEPLETED OIL WELL.

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

RECEIVED
OCT - 2 2006
KCC WICHITA

Form CP-2/3

[Signature]