

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20693-00-00
Spot: SENWNW Sec/Twnshp/Rge: 27-2S-42W
900 feet from N Section Line, 905 feet from W Section Line
Lease Name: CARLA Well #: 2-27
County: CHEYENNE Total Vertical Depth: 5050 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	389		320 sx cmt.

\$104.13

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/11/2006 5:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEITH VANPELT Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 110 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 09/11/2006 7:45 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 2850' w/35 sxs.
2nd. Plug at 440' w/40 sxs.
3rd. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 10/6/06
SER. NO. 2007060648

RECEIVED
OCT - 5 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

100

Signed Bruce Basye
(TECHNICIAN)

OCT 03 2006

pet