

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24095-00-01

Spot: NWSENWSW

Sec/Twnshp/Rge: 36-11S-20W

1815 feet from S Section Line,

4455 feet from E Section Line

Lease Name: SCHOENTHALER OWWO

Well #: 1

County: ELLIS

Total Vertical Depth: 3780 feet

Operator License No.: 32016

Op Name: WELLS, RODGER D. DBA PIONEER RES

Address: 177 W. LINESTONE RD.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3779	0	w/525 sxs cmt
SURF	8.625	218	0	w/175 sxs cmt

\$122.85

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/29/2006 9:00 AM

Plug Co. License No.: 31073

Plug Co. Name: MAIER WELL SERVICE, INC.

Proposal Rcvd. from: TOM MAIER

Company: PIONEER RESOURCES

Phone: (785) 544-5556

Proposed
Plugging
Method:

Ordered out 190 sxs 60/40 pozmix - 10% gel - 500# hulls - 20 sxs gel.
DV Tool at 1520'.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/29/2006 12:00 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

RIH to 3624' - pumped 20 sxs gel followed with 30 sxs cement.
Pulled tubing to 1945' - pumped 140 sxs cement with 500# hulls - circulated cement.
Tied onto 5 1/2" - pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

INVOICED
DATE 10/6/06
2007060651

Remarks: ALLIED CEMENTING COMPANY-TICKET #22030.

Plugged through: TBG

District: 04

Signed

Marvin Mills


(TECHNICIAN)

RECEIVED
Form CP-2/3
OCT - 5 2006

KCC WICHITA
PHT

OCT 03 2006

ASH-BIE OIL COMPANY 36-11-20W
 BOX 132 #1 SCHOENTHALER 'OWWO' NW SE NW SW
 ELLIS, KS. 67637
 CONTR UNKNOWN CTY ELLIS
 GEOL FIELD WC(STELLA DISC)
 ELV 2125 KB SPD E6/15/86 CARD ISSUED 3/12/87 IP P 24 BOPD, NW
 2120 GL SIMP 3714-3720
 API 15-051-24,095 (NEW PAY)



LOG	Top	Depth/Datum
ANH		1492+ 633
B/ANH		1550+ 575
TOP		3156-1031
HEEB		3379-1254
TOR		3399-1274
LANS		3416-1291
STARK		3607-1482
BKC		3645-1520
MARM		3686-1561
SIMP		3713-1588
ARB		3744-1619
ORTD		3780-1655

OLD INFO: OPERATOR SAME, WELL NAME SAME, SPD 11/28/84, DRLG COMP 12/11/84, SET 8 5/8 " 218 / 175 SX, 5 1/2 " 3779 / 525 SX, MULTI STAGE TOOL AT 1520, COMP AS P 25 BOPD, NW, ARB 3744-3747 (CARD ISSUED 4/25/85), CONTR: HELBERG OIL CO., GEOL: RANDY DAVIS
 LT STN - TR MUD STN, FAINT ODOR IN TOPEKA DOL FROM 3208-52
 SLI STNG & SHOW LIVE OIL, WK ODOR IN TOPEKA LM FROM 3342-50
 V LT SPTY STN, NO ODOR IN LKC LM FROM 3422-26
 SHOW HVY STN, TR GLOBULAR OIL, WK ODOR IN LKC LM FROM 3596-98
 SATR STN & GD SHOW LIVE OIL, STR ODOR IN MARM LM FROM 3695-3704
 LT STRKD STN - MOD SATR TR OIL, LT SHOW LIVE OIL, TR-GD ODOR IN ARB DOL FROM 3744-50
 V LT STN & SLI TR OIL ON FRESH BRK, WK - FR ODOR IN ARB DOL FROM 3762-80

(over)

DST (1) 3433-3465 (LANS) / 30-60-45-90, REC 120' MW, SIP 975-954#, FP 52-63 / 74-84#, HP 1918-1866#, BHT 105°
 DST (2) 3479-3505 (LANS) / 30-30-30-30, REC 1116' MSW, SIP 861-840#, FP 105-413 / 487-570#, HP 1877-1835#, BHT 106°
 DST (3) 3711-3726 (SIMP) / 30-45-60-90, 62' GIP, REC 124' CLEAN OIL, 620' SLI MDY OIL, SIP 1088-1078#, FP 52-137 / 190-307#, HP 2136-2033#, BHT 108°
 MICT - CO, PF (ARB) 3744-3747, W / 4 SPF, AC 250 GAL (MCA), SWB DWN, SO, POP, P 25 BOPD, NW, 12/27/84
 NEW INFO: PROD DECL, REWORKED E 6/15/86, MICT - CO, SET BP ABOVE ARB (DEPTH NA), PF (SIMP) 3714-3720 (EST), SO, NAT, POP, P 24 BOPD, NW