

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21301-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 16-17S-1W
992 feet from S Section Line, 4463 feet from E Section Line
Lease Name: EVERHART Well #: 1
County: MCPHERSON Total Vertical Depth: 2685 feet

Operator License No.: 6819
Op Name: SCOTT'S WELL SERVICE INC
Address: PO BOX 136
ROXBURY, KS 67476

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2685		110 SX
SURF	8.625	250		180 SX
T1	2.875	2616		

87 26

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: DWIGHT EVERHART Company: SCOTT'S WELL SERVICE INC Phone: (785) 254-7828

Proposed Plugging Method: Sand to 50' above perms and cap w/ 5 sxs. Pull pipe and set bridge at 300'. Dump slurry mix to fill from 300' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 08/31/2006 11:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 2550' and capped with 5 sacks of cement. Pulled pipe and set bridge at 309'.
Dumped 7-1/2 yds of slurry mix to fill to surface.

Smokey Valley Concrete #015647

7-1/2 yds slurry mix total -- 22 sxs per yd w/ 10% sand

Perfs:

Top	Bot	Thru	Comments
2616	2620		

RECEIVED
KCC DISTRICT #2
SEP 14 2006
WICHITA, KS

INVOICE
DATE 10-11-06
2007060681

Remarks:

Plugged through: CSG

District: 02

Signed Greg Eves

(TECHNICIAN)

a

RECEIVED
OCT 10 2006
KCC WICHITA

Form CP-2/3

PKT