

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-19171-00-01  
Spot: SWSWSW Sec/Twnshp/Rge: 22-21S-9W  
395 feet from S Section Line, 5093 feet from E Section Line  
Lease Name: ALDEN Well #: 0-13  
County: RICE Total Vertical Depth: 3333 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HIGHWAY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3313		445
SURF	16	49		

\$ 108.32

Well Type: GSO UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/06/2006 2:30 PM  
Plug Co. License No.: 33728 Plug Co. Name: KING'S WELL SERVICE, LLC  
Proposal Revd. from: TERRY WALL Company: SOUTHERN STAR CENTRAL GAS P Phone: (580) 363-7316

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DOUG LOUIS WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/06/2006 5:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Pumped 225 sacks of cement in two stages: 1st stage from 2700' to 2000' with 75 sacks of cement and 2nd stage from 2400' to 2000' with 75 sacks of cement through tubing. Shot off 7" casing at 1900' and pulled out. Ran tubing to 1900' and pumped 50 sacks of cement. Pulled tubing to 1200' and pumped 75 sacks of cement. Pulled tubing to 750' and pumped 75 sacks of cement. Pulled tubing to 500' and circulated cement to surface.

Allied #23806  
Copeland #C-030606  
60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
2642	2661		
2626	2636		
2617	2622		
2461	2485		
2439	2447		

RECEIVED  
KCC DISTRICT #2  
SEP 14 2006  
WICHITA, KS

INVOICED

OATB 10-11-06  
200 7060682

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
OCT 10 2006 Form CP-2/3  
KCC WICHITA PST