

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02984-00-01
Spot: NESESE Sec/Twnshp/Rge: 5-8S-17W
900 feet from S Section Line, 330 feet from E Section Line
Lease Name: ECKERT Well #: 4
County: ROOKS Total Vertical Depth: 916 feet

Operator License No.: 31171
Op Name: CONTINENTAL OPERATING CO.
Address: 1221 MCKINNEY - SUITE 3700
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3353	590	w/unknown sxs cmt
SURF	8.625	117	0	w/unknown sxs cmt

\$ 35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2006 1:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RALPH BRUNGARDT Company: CONTINENTAL OPERATING COM Phone: (785) 735-4645

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel with 300# hulls.
Drilled to top of old 5 1/2" casing at 590'. Ran 5 1/2" casing to 590' with 6 5/8" collar.
Drilled out inside of 5 1/2" casing to 916'. Hit tubing and cement.
Unable to get past 916'. Decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2006 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Pulled 5 1/2" casing back out from 590' and laid down.
Ran 2 7/8" to 590' - unable to wash back to 916'.
Allied pumped 160 sxs 60/40 pozmix - 10% gel with 300# hulls - circulated cement.
PTOH. Topped 8 5/8" off with 15 sxs cement - hole full.
Note: Top of old 5 1/2" casing 590' with junk in hole at 916'.

Perfs:

INVOICED
DATE 10-13-06
NO. 2007060687

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100

Signed Richard Williams
(TECHNICIAN)

OCT 09 2006

RECEIVED
Form CP-2/3
OCT 12 2006
KCC WICHITA
PKA