

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22749-00-01
Spot: N2SWNWSE Sec/Twnshp/Rge: 5-8S-17W
1800 feet from S Section Line, 2310 feet from E Section Line
Lease Name: STAMPER Well #: 2
County: ROOKS Total Vertical Depth: 1740 feet

Operator License No.: 31171
Op Name: CONTINENTAL OPERATING CO.
Address: 1221 MCKINNEY - SUITE 3700
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3333	1808	165 SX
SURF	8.625	1219	0	425 SX

\$56.55

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2006 9:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: RAPLH BRUNGARDT Company: CONTINENTAL OPERATING CO. Phone: (785) 735-4645

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2006 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 1648'. Tagged bottom - pulled one joint to 1621'.
Allied rigged to tubing - pumped 80 sxs heavy mud, followed with 100 sxs 60/40 pozmix and 200# hulls mixed in.
Pulled tubing to 715'. Allied rigged to tubing - pumped 150 sxs cement with 200# hulls mixed in to circulated cement to surface.
Pulled tubing - hole standing full of cement.
Backside full from previous plug.

Perfs:

Top	Bot	Thru	Comments
3206	3208		
3145	3147		
3050	3052		

Remarks: ALLIED CEMENTING COMPANY-TICKET #21375.

INVOICED
DATE 10-13-06
WV. NO. 2007060687

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

12

OCT 05 2006

RECEIVED
Form CP-2/3
OCT 12 2006
KCC WICHITA
[Signature]

REPLACEMENT CARD

GRAHAM-MICHAELIS CORPORATION

P.O. BOX 247
WICHITA, KS. 67201

#2-5 STAMPER


5-8-17W
150' N,
C SW NW SE

CONTR RED TIGER DRILLING

CTY ROOKS

GEOL LARRY BOOKLESS

FIELD LONE STAR



ELV 1874 KB SPD 9/1/85 CARD ISSUED 10/31/85 IP P 25 BOPD, TR WTR
1869 GL DRLG COMP 9/10/85 LKC 3050-3208 OA
 API 15-163-22,749

LOG	Tops	Depth/Datum	
HEEB	3004-1130	8 5/8 " 1226 / 425SX, 5 1/2 " 3333 / 165SX DST (1) 2998-3065 (TOR) / 45-60-30-90, REC 20' M, SIP 861-838#, FP 56-56 / 67-67#
TOR	3027-1153	DST (2) 3070-3150 (LKC) / 60-45-45-90, REC 80' M, SIP 407-441#, FP 67-67 / 90-90#
LANS	3047-1173	DST (3) 3191-3290 (ARB) / 60-45-60-90, REC 206' M, SIP 836-824#, FP 70-160 / 128-163#
ARB	3329-1455	DST (4) 3314-32 (ARB) / 45-60-30-90, REC 20' M, 62' SOCM (8% OIL, 78% M, 14% W), SIP 559-548#, FP 46-46 / 58-58#
RTD	3332-1458	MICT - CO, (ARB OH), SWB DWN, SO, PF (LKC) 3050-52, 3145-47 & 3206-08, AC 750G, SWB DWN, SO, SET 2 7/8 " TBG AT 3304, POP, P 25 BOPD & WTR, 10/10/85 COMMINGLED
LTD	3337-1463	

CORRECTION: 11/21/85 - CORRECTED ARB TOP - WAS ARB 3229-1355