

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22075-00-01
Spot: SWSWNW Sec/Twnshp/Rge: 33-16S-13W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BRADSHAW OWWO Well #: 1-A
County: BARTON Total Vertical Depth: 3401 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3395	0	w/unknown sxs cmt
SURF	8.625	240	0	w/unknown sxs cmt

\$ 110.53

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2006 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: CHARLES R. RAMSAY Company: H&C OIL OPERATING, INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered out 270 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level 1550'. PBTD 3170'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/03/2006 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1822'. Allied pumped 160 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled tubing to 880'. Allied pumped 85 sxs cement with 200# hulls - circulated cement.
PTOH. Allied topped casing off with 20 sxs cement - casing full.
5 1/2" x 4 1/2" annulus - full of cement.
8 5/8" x 5 1/2" annulus - full of cement.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

INVOICED
DATE 10-13-06
INV. NO 2007060692

District: 04

Signed Richard Williams
(TECHNICIAN)

DD

PPT

OCT 04 2006

RECEIVED
Form CP-2/3
OCT 12 2006
KCC WICHITA

