

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22141-00-00
Spot: NESWSE Sec/Twnshp/Rge: 33-15S-11W
1155 feet from S Section Line, 1815 feet from E Section Line
Lease Name: FOSTER A Well #: 3
County: RUSSELL Total Vertical Depth: 3244 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE ROAD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3238	0	190 SX
SURF	8.625	655	0	325 SX

\$ 105.43

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/02/2006 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/02/2006 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

05/02/2006
Pumped 50 sxs 60/40 pozmix - 10% gel cement down backside.
Max. P.S.I. 300#. S.I.P. 100#.
Pumped 70 sxs cement down casing.
Pump truck broke down.
Displaced cement to bottom of hole with water.
10/05/2006
Ran tubing to 1100' - circulated with 100 sxs cement with 200# hulls.
POOH. Topped off with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3238	3244		

INVOICED
DATE 10-13-06
INV. NO. 2007060696

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Case Morris
(TECHNICIAN)

OCT 09 2006

RECEIVED
OCT 12 2006
KCC WICHITA

Vertical text on the left margin, possibly a reference or date.

Vertical text on the left margin, possibly a reference or date.

Vertical text on the left margin, possibly a reference or date.

FRONTIER OIL COMPANY

1720 KSB&T BUILDING

#3 "A" FOSTER

33-15-11W

NE SW SE

WICHITA, KS 67202

CONTR RED TIGER DRILLING CO.

CTY RUSSELL

GEOLOGICAL STEVE D. PARKER

FIELD DAVIDSON

ELV 1779 KB SPD 6/9/83


CARD ISSUED 8/18/83

IP OIL WELL

1774 GL

ARB 3238-3244

API 15-167-22,141



SMP	Tops	Depth Datum
ANH	648	+ 1131
BRNVLE	2178	- 399
GR HAV	2217	- 438
DOVER	2242	- 463
TARK	2287	- 508
ELM	2346	- 567
HOW	2484	- 705
TOP	2562	- 783
HEEB	2815	-1036
TOR	2833	-1054
DOUG	2845	-1066
BR LM	2906	-1127
LANS	2927	-1148
BKC	3170	-1391
ARB	3236	-1457
RTD	3244	-1465

8 5/8 " 655/325SX; 5 1/2 " 3238/190SX
 DST (1) 2940-75 (LKC) / 30-30-30-30, REC 30' M, SIP 805-654#, FP 41-82 / 72-92#
 DST (2) 3166-3240 (LKC) / 30-30-30-30, REC 20' OIL SPTD M, SIP 755-534#, FP 72-82 / 72-82#
 DST (3) 3168-3244 (LKC) / 60-30-60-30, REC 75' SO & GCM, 305' HO & GCM, SIP 799-799#, FP 81-183 / 183-254#
 MICT - CO, (ARB OH), ONFU 700' OIL, T&R, POP

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS