

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

113-05473-00-01

Lease Operator: Te-Pe oil & gas
Address: Box 522 Canton, Ks.
Phone: (620) 628-4428 Operator License #: 5920
Type of Well: enhr. Docket #: E-9787
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 8-15-06 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
mississippian Depth to Top: 2913 Bottom: 3168 T.D. 3410
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-417134
Lease Name: Lovett FA *KCC Pkt 10/12/06 per district.*
Well Number: 5 *KCC Pkt 10/12/06 per OPS.*
Spot Location (QQQQ): _____ - se - SW - SW
330 308 Feet from North / South Section Line
4200 4417 Feet from East / West Section Line
Sec. 13 Twp. 19 S. R. 02 East West
County: mcperson
Date Well Completed: 1/17/34 *original*
Plugging Commenced: 9/24/06
Plugging Completed: 9/27/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
mississippian	water	219	0	13 3/8	219	0
viola	water	3389	0	7	3389	0


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to top of fish at 2760 ft. and spot 35 sks. of cement @2760 ft. Pull tubing. Bridge at 475ft.in 7" casing. Perforate 7" casing at 450 ft. Run tubing to 425 ft. Pump cement down tubing and circulate cement, fill 7" casing with cement, had circulation up 7x13" annulus but did not get cement to top. Pull tubing. run 1" tubing down 7x13" annulus to top of cement and circulate annulus full of cement to top of casing. Pull tubing. Run tubing into 7" casing to top of cement and circulate cement to top of casing. Pull tubing.

Name of Plugging Contractor: Cyclone Well Service inc. License #: 3038
Address: box 522 Canton, Ks.
Name of Party Responsible for Plugging Fees: Te-Pe oil & Gas
State of Kansas County, McPherson, ss.
Terry P. Bandy (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Terry P. Bandy
(Address) Box 522 Canton, Ks. 67428



SUBSCRIBED and SWORN TO before me this 6th day of October, 20 06
Cynthia G. Beneke My Commission Expires: 5-15-2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 10 2006
KCC WICHITA