

Operator Name: Quest Cherokee, LLC Lease Name: Brant, Jerry W. Well #: 31-1
 Sec. 31 Twp. 28 S. R. 18 East West County: Neosho

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

Comp. Density/Neutron Log
 Dual Induction Log
 Gamma Ray/Neutron Log

Log Formation (Top), Depth and Datum Sample

Name Top Datum
 See attached

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	11"	8-5/8"	20#	21.3	"A"	6	
Production	6-3/4"	4-1/2"	10.5#	1107	"A"	140	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing				
___ Plug Back TD				
___ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)		Depth
		4	649-653/662-667/732-734/754-757/794-796/1051-1056	
		400gal 15%HCL w/ 26 bbls 2%kcl water, 538bbls 2%kcl, biocide, 12100# 20/40 sand	794-796/754-757	
			732-734	
		400gel 15% acid w/ 55bbls 2%kcl water, 300bbls, no gel, 2%kcl, biocide, 52sks 20/40 sand	1051-1056	

TUBING RECORD Size 2-3/8" Set At 1064.92 Packer At n/a Liner Run Yes No

Date of First, Resumerd Production, SWD or Enhr. 3/15/06 Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours Oil Bbls. n/a Gas Mcf 19mcf Water Bbls. 30bbls Gas-Oil Ratio Gravity

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.) METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) Production Interval

RECEIVED
 KANSAS CORPORATION COMMISSION
 APR 13 2006

CONSERVATION DIVISION
 WICHITA, KS

QUEST

Resource Corporation

211 W. 14TH STREET,
CHANUTE, KS 66720
620-431-9500

TICKET NUMBER **1107**

FIELD TICKET REF # _____

FOREMAN Dwayne Joe

TREATMENT REPORT & FIELD TICKET CEMENT

DATE	WELL NAME & NUMBER			SECTION	TOWNSHIP	RANGE	COUNTY
11-17-05	Jerry Plant W 31-1			31	28	18	NO
FOREMAN / OPERATOR	TIME IN	TIME OUT	LESS LUNCH	TRUCK #	TRAILER #	TRUCK HOURS	EMPLOYEE SIGNATURE
Dwayne Joe	2:30	6:45	NO	903388		4	<i>[Signature]</i>
Wes	2:30	6:15	NO	903197		3 3/4	<i>[Signature]</i>
Maurick	2:30	6:40	NO	903206		4 1/4	<i>[Signature]</i>
Daniel	2:30	6:30	NO	903100		4	<i>[Signature]</i>
Mac	2:30	6:30	NO	903400	932705	4	<i>[Signature]</i>
Randall	2:00	6:30	NO	903139	T28	4 1/2	<i>[Signature]</i>

JOB TYPE Long string HOLE SIZE 6 3/4 HOLE DEPTH 1112 CASING SIZE & WEIGHT 4 1/2 16.5 #
 CASING DEPTH _____ DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.5 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 17.2 DISPLACEMENT PSI _____ MIX PSI _____ RATE 3.5

REMARKS:

Wash Down 100' of casing then circulate 4 sk. Perm Gel to surface
 Then Pump 10 Bbl Dye Followed 150 sacks cement to get dye back
 Stop and wash out Pump then Pump Wiper Plug to Bottom
 and Set Float Shoe

~~Very~~ Very Dirty Hole

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION OF SERVICES OR PRODUCT	TOTAL AMOUNT
	1107	4 1/2 Casing 10.5 #	
	1	4 1/2 Float Shoe Spring and Ball Type	
	4	Centralizers	
903388	4 1/4 hr	Foreman Pickup	
903197	3 3/4 hr	Cement Pump Truck	
903206	4 1/4 hr	Bulk Truck	
1104	140	Portland Cement	
903139	4 1/2 hr	5050 Poz Blend Cement Casing Tractor	
T28	4 1/2 hr	OWC Blend Cement Casing Trailer	
1110	15	Gilsonite	
1107	1.5	Flo-Seal	
1118	2	Premium Gel	
1215A	1 Gal	KCL	
1211B	3	Sodium Silicate Col Chloride	
1123	7	City Water	
903400	4	Transport Truck	
932705	4	Transport Trailer	
903100	4	80 Vac	

RECEIVED
KANSAS CORPORATION COMMISSION

APR 13 2006

CONSERVATION DIVISION
WICHITA, KS