

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-31057-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 9-33S-17E  
400 feet from S Section Line, 2140 feet from E Section Line  
Lease Name: MCNICKLE Well #: 15-9  
County: MONTGOMERY Total Vertical Depth: 1060 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: P.O. BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	20		6 SX CMT.

\$ 35.00

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2006 8:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Revd. from: SHIRLEY STOTLER Company: COLT ENERGY INC Phone: (620) 365-3111

Proposed Plugging Method: Run cement string to TD and fill well from bottom to top thru cement string.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 06/27/2006 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A two inch cement string was lowered to 1060 ft. 10 sacks of 60/40 poz/mix was placed at 1090 ft. A gel plug was placed to 525 ft. The cement string was raised to 525 ft and 10 sacks of cement placed at 525 ft. A gel plug was placed to 250 ft. The cement string was raised to 250 ft and the well filled with cement from 250 ft to surface. A total of 70 sacks of cement were used to plug well. A representative of Colt stated the LS was never cemented in because this is dry hole.

Perfs:

RECEIVED  
KCC DISTRICT #3  
OCT 2 2006 AMB  
CHANUTE, KS

INVOICED  
DATE 10-9-06  
BY 20070606.53

Remarks:

Plugged through: OH

District: 03

Signed Alan Dunning  
(TECHNICIAN)

RECEIVED  
Form CP-2/3  
OCT - 8 2006  
KCC WICHITA  
PRT