

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23379-00-00
Spot: SWNW Sec/Twnshp/Rge: 21-12S-15W
1980 feet from N Section Line, 675 feet from W Section Line
Lease Name: HOLLAND A Well #: 1
County: RUSSELL Total Vertical Depth: 3375 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	590		

\$109.69

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/25/2006 1:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 145 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES WitnessType: NONE
Date/Time Plugging Completed: 09/25/2006 3:45 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

1st. Plug at 3275' w/25 sxs.
2nd. Plug at 900' w/25 sxs.
3rd. Plug at 600' w/60 sxs.
4th. Plug at 40' w/10 sxs - 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED

DATE 10-9-06
INV. NO. 20070606-54

RECEIVED

OCT - 6 2006

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

Roger L. Moses
(TECHNICIAN)

Form CP-2/3

OCT 05 2006

PR