

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-00109-00-02  
Spot: NWNWSW Sec/Twnshp/Rge: 23-19S-1E  
2316 feet from S Section Line, 5059 feet from E Section Line  
Lease Name: WASEMILLER Well #: 1  
County: MARION Total Vertical Depth: 3495 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2932		
PROD	4.5	3495		
SURF	8.625	150		

\$ 113.59

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2006 8:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Revd. from: JAKE SIGEL Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Pumping Method: Pump 35 sxs @ 2460'; pull tbg to 400' and circ to surf. Ensure that backside is circulated with cement.

Plugging Proposal Received By: GREG EVES WitnessType: NONE  
Date/Time Plugging Completed: 09/01/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Ran tubing to 2460' and pumped 35 sacks of cement. Pulled tubing to 400' and pumped 55 sacks of cement to circulate to surface. Ran 1" tubing down backside and pumped 33 sacks of cement. Plug fell and required 27 sacks of cement to top off.

150 sxs  
60/40 posmix with 4% gel  
Copeland CP-30663-IN

Perfs:

RECEIVED  
KCC DISTRICT #2  
SEP 27 2006  
WICHITA, KS

INVOICED  
DATE 10-11-06  
TEL NO 200-706-0606

Remarks:

Plugged through: TBG

District: 02

Signed Greg Eves  
(TECHNICIAN)

RECEIVED Form CP-2/3  
OCT 10 2006  
KCC WICHITA

*[Handwritten mark]*

*[Handwritten mark]*