

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-02076-00-00
Spot: NESESE Sec/Twnshp/Rge: 21-18S-1W
1170 feet from S Section Line, 463 feet from E Section Line
Lease Name: STATE F Well #: 2
County: MCPHERSON Total Vertical Depth: 2786 feet

Operator License No.: 31448
Op Name: EVERHART, LAWRENCE D. DBA E & E
Address: PO BOX 451
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2786	1226	
SURF	8.625	120		

\$ 90.55

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/22/2006 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DWIGHT EVERHART Company: E & E OIL Phone: (620) 654-8140

Proposed Plugging Method: Sand to 50' above perms; cap w/ 4 sxs; pull pipe to 300' and circ to surf.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 08/22/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 2600' and capped with 5 sacks of cement. Pulled 1226' of pipe. Set bridge at 300'. Dumped 6-1/2 yds of slurry mix to fill to surface. Plug fell to 72'. Topped off with 2 yds of slurry mix.

Smokey Valley Concrete #015515 and #015551

8-1/2 yds total -- slurry mix = 22 sxs/yd w/ 10% sand

Perfs:

Top	Bot	Thru	Comments
2750	2785		

**RECEIVED
KCC DISTRICT #2
SEP 14 2006
WICHITA, KS**

INVOICED
DATE 10-11-06
INV. NO. 2007060607

Remarks:

Plugged through: CSG

District: 02

Signed Greg Eves
(TECHNICIAN)

RECEIVED
OCT 10 2006
KCC WICHITA

Form CP-2/3