

Td: 1 31012. 7-24  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 007-22,476-00-00  
NW NE SW, SEC. 11, T 30 S, R 12 W/EX

470 2310 feet from N section line  
1750 1650 feet from W section line  
*per RB Dins for 10/11/04*

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047  
Operator: Rupe Oil Company, Inc.  
Name: \_\_\_\_\_  
Address: 434 Ohio  
P.O. Box 783010  
Wichita, KS 67278-3010

Lease Name Kumberg C Well # 3-11  
County Barber 113.43  
Well Total Depth 3490 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well DH Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Ste. 202, Wichita, KS 67202

Company to plug at: Hour: 12:30 a.m. Day: 24 Month: 7 Year: 19 95

Plugging proposal received from Joe Livingston

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 740' with 50 sx cement,

2nd plug at 260' with 50 sx cement, 3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:35 a.m. Day: 24 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 740' with 50 sx cement,

2nd plug at 260' with 50 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 65/35 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
(check this box) observe this plugging.

DATE 7-28-95

INV. NO. 43191  
7-24

Signed Steve Durrant (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 26 1995

CONSERVATION DIVISION  
WICHITA, KS