

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24237-00-00
Spot: SWSE Sec/Twnshp/Rge: 23-19S-19E
660 feet from S Section Line, 2100 feet from E Section Line
Lease Name: PEINE TRUST Well #: 23-34
County: ANDERSON Total Vertical Depth: 1235 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1231		165 SX CMT
SURF	8.625	22		4 SX CMT

\$ 40.14

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/24/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Pumping Method: PUMP 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SACK COTTON SEED HULLS FROM PBTD TO 900'; SPOT 9.5 PPG BENTONITE MUD FROM 900' TO 150'; SPOT 60/40 CLASS A/POZIMIX CEMENT FROM 150' TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 05/24/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

ESTABLISH INJECTION RATE THROUGH CASING AT 4 BBL. PER MINUTE AT 200 PSI. PUMP 124 SACKS OF 60/40 POZ MIX AND SHUT IN. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1156	1159		
1142	1144		
1136	1139		
1129	1132		

RECEIVED
KCC DISTRICT #3
OCT 3 2006 FG
CHANUTE, KS

INVOICED

DATE 10-11-06
WV. NO 2007060675

Remarks: OPERATER PLUGGED WELL.

Plugged through: CSG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

RECEIVED
OCT 10 2006
KCC WICHITA

Form CP-2/3

PKT