

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20852-00-00  
Spot: SW Sec/Twnshp/Rge: 33-17S-9W  
1232 feet from S Section Line, 3973 feet from E Section Line  
Lease Name: ROLFS FARMS Well #: 2  
County: ELLSWORTH Total Vertical Depth: 3235 feet

Operator License No.: 33748  
Op Name: ORTH. LOREN DBA GUSHER OIL  
Address: 460 AVE E  
BUSHTON, KS 67427

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3231		125 SX CMT
SURF	8.625	347		175 SX CMT

\$ 105.14

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/30/2006 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand to 3180' and cap w/ 5 sxs. Pull casing to 1200' and pump 35 sxs. Pull to 850' and pump 35 sxs. Pull to 400' and circ to surf.

Plugging Proposal Received By: DAVE WERTZ Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/30/2006 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 3150' and capped with 5 sacks of cement. Pulled casing to 1190' and pumped 35 sacks of cement. Pulled casing to 860' and pumped 35 sacks of cement. Pulled casing to 420' and pumped 120 sacks of cement to circulate to surface.

Allied Cement #23803

190 sxs total

60/40 posmix with 4% gel

Perfs:

**RECEIVED**  
**KCC DISTRICT #2**  
**SEP 14 2006**  
**WICHITA, KS**

Remarks:

Plugged through: CSG

INVOICED  
DATE 10-11-06  
WEL. NO. 2007060676

District: 02

Signed

Greg Eves  
(TECHNICIAN)

**RECEIVED**  
**OCT 10 2006**  
**KCC WICHITA**

Form CP-2/3

2

RET