

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20870-00-00
Spot: E2SESE Sec/Twnshp/Rge: 32-17S-9W
703 feet from S Section Line, 404 feet from E Section Line
Lease Name: CHASE Well #: 2
County: ELLSWORTH Total Vertical Depth: 3350 feet

Operator License No.: 33748
Op Name: ORTH, LOREN DBA GUSHER OIL
Address: 460 AVE E
BUSHTON, KS 67427

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3747		
SURF	8.625	302		

\$108.88

Well Type: SWD UIC Docket No: D23237.0 Date/Time to Plug: 08/31/2006 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand to 50' above top perforations and cap with 5 sxs cement. Pump 35 sxs at 1200' and pump 35 sxs at 850'. Circulate from 350' to surface.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 08/31/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded bottom to 3190' and capped with 5 sacks of cement. Pulled pipe to 1200' and pumped 35 sacks of cement. Pulled pipe to 850' and pumped 35 sacks of cement. Pulled pipe to 350' and pumped 85 sacks of cement to circulate to surface.

Allied Cement #23839

155 sxs total
60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3296	3325		

RECEIVED
KCC DISTRICT #2
SEP 14 2006
WICHITA, KS

INVOICED

Remarks:

Plugged through: CSG

DATE 10-11-06
NO. 2007060674

District: 02

Signed

Greg Eves

(TECHNICIAN)

RECEIVED
OCT 10 2006
KCC WICHITA

Form CP-2/3

a

PKY