

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20665-00-00

Spot: NESENW

Sec/Twnshp/Rge: 2-19S-1W

3679 feet from S Section Line,

3041 feet from E Section Line

Lease Name: DECKER

Well #: 1

County: MCPHERSON

Total Vertical Depth: 2901 feet

Operator License No.: 32381

Op Name: KREHBIEL, JAY DBA K & S OIL CO.

Address: 1520 N GRIMES
MCPHERSON, KS 67460

String Size Depth (ft) Pulled (ft) Comment

PROD 5.5 2900 50 SX

SURF 8.625 168 125 SX

\$ 94.28

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/28/2006 1:00 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed
Plugging
Method:

Sand to 50' above perms and cap w/ 5 sxs cement. Set bridge at 400' and dump slurry mix to cement from 400' to surface.

Plugging Proposal Received By: VIRGIL CLOTHIER

WitnessType: PARTIAL

Date/Time Plugging Completed: 08/28/2006 4:00 PM

KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 2780' and capped with 5 sacks of cement. Perforations were from 2847' to 2855'. Pulled 1368' of pipe and bailed fluids to 390'. Dumped slurry mix to fill from 390' to surface.

Smokey Valley Concrete #015647
7-1/2 yds total -- 22 sx/yd w/ 10% sand

Perfs:

Top	Bot	Thru	Comments
2847	2855		MISSISSIPPI

**RECEIVED
KCC DISTRICT #2
SEP 14 2006
WICHITA, KS**

INVOICED

Remarks:

Plugged through: CSG

DATE 10-11-06
NO. 2007060673

District: 02

Signed Greg Eves

(TECHNICIAN)

RECEIVED

OCT 10 2006

KCC WICHITA

Form CP-2/3

[Handwritten mark]

[Handwritten mark]