

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24231-00-00
Spot: S2NWNE Sec/Twnshp/Rge: 34-19S-19E
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: LANKARD Well #: 34-31
County: ANDERSON Total Vertical Depth: 1220 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1217		165 SX CMT
SURF	8.625	20		4 SX CMT

\$ 39.65

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/05/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBD TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 06/05/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING AND TOP OFF WELL. PUMP TOTAL OF 134 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1124	1126		
1121	1123		
1116	1119		
1110	1113		
1077	1079		
1051	1053		
1038	1040		
898	900		
884	886		
840	842		
769	771		
746	748		
697	699		
662	665		
589	591		
411	413		
381	383		

RECEIVED
KCC DISTRICT #3
OCT 3 2006 FG
CHANUTE, KS

Remarks: OPERATER PLUGGED WELL

Plugged through: TBG

INVOICED
DATE 10/11/06
NO. 2007060675

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

RECEIVED
OCT 10 2006
KCC WICHITA

PKT