

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24234-00-00
Spot: S2NENE Sec/Twnshp/Rge: 34-19S-19E
990 feet from N Section Line, 860 feet from E Section Line
Lease Name: LANKARD Well #: 34-41
County: ANDERSON Total Vertical Depth: 1215 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1201		165 SX CMT
SURF	8.625	22		4 SX CMT

\$ 39.49

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/30/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZMIX CEMENT WITH 0.5 SAX COTTON SEED HULLS FROM PBDT TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 05/30/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING AND TOP OFF WELL. PUMP TOTAL OF 119 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1139	1141		
1123	1125		
1118	1120		
1111	1114		
1077	1079		
954	956		
906	908		
891	893		
863	866		
850	852		
777	779		
751	753		
702	704		
668	670		
595	597		
418	421		
382	385		

RECEIVED
KCC DISTRICT #3

OCT 3 2006 FG

CHANUTE, KS

INVOICED

DATE 10-11-06
SERIAL 2007060675

Remarks: WELL PLUGGED BY OPERATER.

Plugged through: TBG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

RECEIVED
OCT 10 2006
KCC WICHITA

PKT