

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-24236-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 26-19S-19E  
1300 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: KUESER Well #: 26-31  
County: ANDERSON Total Vertical Depth: 1233 feet

Operator License No.: 33138  
Op Name: MERITAGE KCM EXPLORATION, LLC  
Address: INDEPENDENCE PLAZA 1050 17TH ST  
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1211		165 SXS CMT
SURF	8.625	22		4 SXS CMT
T1	2.875	1137		

\$ 40.07

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2006 8:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: LARRY BRYANT Company: \_\_\_\_\_ Phone: (970) 301-1411

Proposed Plugging Method: PUMP 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 950'; PUMP 9.5 PPG BENTONITE MUD FROM 950' TO 150'; CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 150' TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 05/25/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

ACCORDING TO CP-4, CASING WAS LOADED TO ESTABLISH INJECTION RATE OF 3 BBL. PER MINUTE AT 500 PSI. MIX AND PUMP 120 SACKS OF 60/40 POZ MIX. SHUT DOWN PUMP AND TOP OFF CASING.

Perfs:

Top	Bot	Thru	Comments
1150	1151		
1143	1146		
1137	1140		

RECEIVED  
KCC DISTRICT #3  
OCT 3 2006  
CHANUTE, KS  
FG

INVOICED

DATE 10-11-06  
# 2007060675

Remarks: WELL PLUGGED BY OPERATER.  
Plugged through: CSG

District: 03

Signed Frank Guilfoyle  
(TECHNICIAN)

RECEIVED  
OCT 10 2006  
KCC WICHITA

Form CP-2/3

PCT