

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07740-00-00
Spot: NESENW Sec/Twnshp/Rge: 5-15S-14W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PHINNEY Well #: 5
County: RUSSELL Total Vertical Depth: 3199 feet

Operator License No.: 33633 *KCC W/H/W*
~~50876~~ *12/10/03*
Op Name: CARTER, JAMES P. DBA J. CARTER OIL
Address: PO BOX 491
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3194	0	w/100 sxs cmt
SURF	8.625	353	0	w/175 sxs cmt

\$ 103.97

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/02/2006 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAN Company: J.CARTER OIL Phone: (785) 483-5696

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2006 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Went outside of casing while trying to clean out well - could not get past 800'.
Ran tubing to 775' - circulated with 100 sxs 60/40 pozmix - 10% gel cement.
POOH. Tied onto casing and pumped 100 sxs cement with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 400#.
Tied onto backside. Blew out multiple holes in 8 5/8".
10/03/2006 - Ran two yards of ready-mix into annulus.

INVOICED
DATE 10-17-06
NOV. 12 2006 0712

Remarks: QUALITY CEMENTING.

Plugged through: CSG

District: 04

M -

Signed _____

Case Morris

(TECHNICIAN)

OCT 09 2006

RECEIVED
Form CP-273

OCT 12 2006

KCC WICHITA *PR*

GABBERT-JONES

#5

PHINNEY

5 15 14W 33
NE SE NW


Contr. _____ RUSSELL County

E 1771 RB Comm. _____ Comp. 6-22-51 IP 25 BOPD

Tops	Depth	Datum
TOP	2682	-911
HEEB	2897	-1126
LANS	2949	-1178
ARB	3193	-1422
T.O.	3199	-1428

Casing
 8 7/8 - 353' w 175 s x s
 5" 3194 DSI 3193 99, 5 M N,
 w 100 s x s 1160' OIL & 70'
 OILY MUD
 2800 OIH

GORHAM POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS