

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-20457-00-01
Spot: NWSWNE Sec/Twnshp/Rge: 36-24S-21E
3810 feet from S Section Line, 2500 feet from E Section Line
Lease Name: HUMPHREY Well #: 42
County: BOURBON Total Vertical Depth: 702 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 6855 S. HAVANA ST., STE 250
CENTENNIAL, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	702	0	
SURF	6.25	20	0	<u>\$ 35.00</u>

Well Type: EOR UIC Docket No: E17316.9 Date/Time to Plug: 05/23/2006 10:00 PM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: DALE MALEY Company: NORSTAR PETROLIUM, INC. Phone: (620) 496-6076

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 702' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 05/23/2006 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 702'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1' PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

Top	Bot	Thru	Comments
641	652	CSG	

RECEIVED
KCC DISTRICT #:

OCT 11 2006 CPT

CHANUTE, KS

INVOICED
DATE 10-17-06
INV. NO. 2007060714

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED Form CP-2/3
OCT 16 2006
KCC WICHITA

PKT