

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19379-00-00

Spot: NWNWNWSE

Sec/Twnshp/Rge: 28-30S-16E

2632 feet from S Section Line,

2498 feet from E Section Line

Lease Name: JOHNSON

Well #: 1

County: WILSON

Total Vertical Depth: 800 feet

Operator License No.: 3830

Op Name: A X & P, INC.

Address: PO BOX 1176

INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20	0	

\$ 35.00

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/28/2004 8:00 AM

Plug Co. License No.: 33422

Plug Co. Name: HOUSEL, RICK DBA RICK'S WELL SERVICE

Proposal Rcvd. from: RICK HOUSEL

Company: RICK'S WELL SERVICE

Phone: (620) 336-2944

Proposed Plugging Method: Perforate tubing and fill from bottom to top thru cement string.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: PARTIAL

Date/Time Plugging Completed: 03/28/2005 12:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The two inch pipe was perforated at 250 ft and 75 ft. A one inch cement string was lowered to 775 ft, gel circulated, and 10 sacks of cement spotted. The cement string was raised and the well filled from 250 ft to surface with cement. The cement string was removed and the well topped off with cement. A total of 82 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KCC DISTRICT #3

OCT 4 2006 AMB

CHANUTE, KS

INVOICED

10-17-06

2007060710

Remarks:

Plugged through: TBG

District: 03

Signed

Alan Dunning
(TECHNICIAN)

RECEIVED

OCT 16 2006

KCC WICHITA

Form CP-2/3

Pkt