

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19380-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 28-30S-16E
2614 feet from S Section Line, 2312 feet from E Section Line
Lease Name: JOHNSON Well #: 4
County: WILSON Total Vertical Depth: 800 feet

Operator License No.: 3830

Op Name: A X & P, INC.

Address: PO BOX 1176
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	20		

\$ 35.00

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/28/2004 8:00 AM

Plug Co. License No.: 33422

Plug Co. Name: HOUSEL, RICK DBA RICK'S WELL SERVICE

Proposal Rcvd. from: RICK HOUSEL

Company: RICK'S WELL SERVICE

Phone: (620) 336-2944

Proposed Plugging Method: Perforate tubing and fill from bottom to top thru cement string.

Plugging Proposal Received By: ALAN DUNNING

Witness Type: NONE

Date/Time Plugging Completed: 03/28/2005 12:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The two inch pipe was perforated at 250 ft and 75 ft. A one inch cement string was lowered to 775 ft, gel circulated, and 10 sacks of cement spotted. The cement string was raised and the well filled from 250 ft to surface with cement. A total of 72 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KCC DISTRICT #3

OCT 4 2006 AMD

CHANUTE, KS

INVOICED

DATE: 10-17-06
REF. NO. 2007.0607.10

Remarks:

Plugged through: TBG

District: 03

Signed

Alan Dunning

(TECHNICIAN)

RECEIVED

OCT 16 2005

KCC WICHITA

Form CP-2/3

PKT