

4-060390

5-09

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-141-20,277-00-00

SW NW NE /4 SEC. 09, 10 S, 12 W
4290 feet from S section line
2310 feet from E section line

Operator license# 5184 Lease Becker well # 1

Operator: Shields Oil Producers, Inc. County Osborne

Address: Shields Building - 326 Main Well total depth 3084 feet ^{100.23}
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Shields Drilling Company License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: 6:00A.M. Day: 9 Month: May Year: 93

Plugging proposal received from: Burton Berry

Company: Shields Drilling Company Phone: 913-483-3141

Were: Order 200 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 6:00A.M., Day: 09, Month: May, Year: 1993

Actual plugging report:
1st. plug at 875' w/25 sxs. - Anhydrite 853' - 886'.
2nd. plug at 635' w/100 sxs. - Dakota 335' - 635'.
3rd. plug at 270' w/40 sxs. - Surface pipe to 217'.
4th. plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 1785 GL

I did and not X observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
5-18-93
MAY 18 1993
DH (agent)
CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3

INVOICED
DATE 5-27-93
INV. NO. 37762