

6-100485

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-141-20,280-00-00

SW SE SW/4 SEC 36, 10 S, 12 W
330 feet from S section line
3630 feet from E section line

Operator license# 05184

Lease: TAYLOR "D" Well # 1

Operator: Shields Oil Producers Inc.

County: OSBORNE

Address: Shields Building, 326 Main
P.O. Box 709
Russell, KS

Well total depth: 3886 feet
Conductor pipe: inch _____ @ _____ feet
Surface pipe: 8 5/8 inch @ 231 feet

126.30

67665

Abandoned Oil well: _____ Gas Well: _____ Input Well: _____ SWD Well: _____ D & A: X

Plugging contractor: SHIELDS DRILLING COMPANY License: 05184

Address: RUSSELL, KANSAS 67665

Company to plug at: Hour: ?? Day: _____ Month: _____ Year: _____

Plugging proposal received from: BURT BEERY

Company: SHIELS DRILLING COMPANY Phone: _____

Were: Spot all plugs through drill with heavy mud between all plugs.

1st plug @ 3886 feet with 25 sacks

Rat hole: 15 sacks

2nd plug @ 715 feet with 25 sacks

Mouse hole: 10 sacks

3rd plug @ 0535 feet with 100 sacks

Wiper plug @ 40 feet

4th plug @ 280 feet with 40 sacks

5th plug @ 40 feet with 10 sacks

Plugging proposal received by: DAVID WANN

Plugging operations attended by agent? All[], Part[], None[X]

Completed: hour: 7:30 PM, Day: 14, Month: October, Year: 1993

Actual plugging report: Hole reported plugged as above

Order 225 sx 60/40 posmix w/ 6% gel and 2 sx celloflake or flowcel.

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1993

Remarks: Elevation: 1682 G Anhydrite depth: 712 feet, Anhy. plug: Y

Dakota plugged: Y Bottom hole plug in place (A/E/N): A

Plugged through drill pipe: Y

Arbuckle: 3864 Cemented by: ALLIED

CONSERVATION DIVISION
Wichita, Kansas

12-20-93

INVOICED

did not[X] observe the plugging.

DAVID WANN
(agent)

DATE DEC 28 1993

INV. NO. 39550

form CP-2/3