

3-31

4-061057

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-141-20,331-00-00

SE NW NE /4 SEC. 09, 10 S, 12 W
4290 feet from S section line
1650 feet from E section line

Operator license# 3956

Lease Becker Well # 1

Operator: Brungardt Oil & Leasing Co.

County: Osborne 100.59

Address: P.O. Box 871
Russell, Kansas 67665

Well total depth 3095 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: Shields Oil Producers License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: 11:00 P.M. Day: 30 Month: March Year: 1997

Plugging proposal received from: Burt Beery

Company: Shields Oil Producers Phone: _____

Were: Order 180 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.
TD in C zone of LKC.

RECEIVED
KANSAS CORP COM
1997 APR -7 AM 11:51
4-7-97

Plugging Proposal Received by: Herb Deines


Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:00 A.M., Day: 31, Month: March, Year: 1997

Actual plugging report:
1st. Plug at 880' w/25 sxs. Anhydrite 860' - 895'.
2nd. Plug at 625' w/80 sxs. Anhydrite 349' - 625'.
3rd. Plug at 260' w/40 sxs. Surface pipe to 208'.
4th. Plug at 40' w/10 sxs.
15 sxs in rathole.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____
Bottom plug(in place): YES _____, CALC _____, NO X Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING _____. Elevation: 1799 GL

I did[] / did not [X] observe the plugging.


(agent)
Form CP-2/3

INVOICED
DATE 4-7-97
INV. NO. 47873