

4-060806

12-22

API Number: 15-141-20,311-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NE SE SW /4 SEC. 09, 10 S, 12 W  
990 feet from S section line  
2970 feet from E section line

Operator license# 6246 Lease: Libal Well # 1

Operator: Bennett & Schulte County: Osborne

Address: P.O. Box 329 Well total depth 3080 100.10 feet  
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 173 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: VonFeldt Drilling Company License# 9431

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 22 Month: December Year: 1995

Plugging proposal received from: Darrell Krier

Company: VonFeldt Drilling Company Phone: 913-483-6446

Were: Order 180 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 2:45 A.M., Day: 22, Month: December, Year: 1995

Actual plugging report:  
1st. Plug at 875' w/25 sxs. - Anhydrite 840' - 865'.  
2nd. Plug at 575' w/80 sxs. - Dakota 305' - 555'.  
3rd. Plug at 225' w/40 sxs. - Surface pipe to 173'.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 8 1996  
1-8-96  
WICHITA, KANSAS

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: 1755 GL

INVOICED

I did [ ], did not [ X ] observe the plugging.

*[Signature]*  
(agent)

DATE JAN 12 1996

INV. NO. 44545

12-22