

4-060766

11-2

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-141-20,309-00-00
100'E.of
N2 N2 NE ~~N2~~ /4 SEC. 09, 10 S, 12 W
~~4950 330 KCC~~ feet from ~~N2~~ section line
1220 feet from E section line

Operator license# 6194 Lease: Becker Well # 1
Operator: E.S.P. Development, Inc. County: Osborne *10374*
Address: 17746 177th Blvd. Well total depth 3192 feet
Paradise, Kansas 67658 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: Shields Oil Producers, Inc. License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 2 Month: November Year: 1995

Plugging proposal received from: Burt Berry

Company: Shields Oil Producers, Inc. Phone: 913-483-3141

Were: Order 180 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:50 P.M., Day: 2, Month: November, Year: 1995

Actual plugging report:

- 1st. Plug at 900' w/25 sxs. - Anhydrite 894' - 925'.
- 2nd. Plug at 625' w/80 sxs. - Dakota 375' - 625'.
- 3rd. Plug at 260' w/40 sxs. - Surface pipe to 208'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 15 sxs.
- Mousehole with 10 sxs.

*Quint 11-16-95
KCC*

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD___ BAD___ Anhy.plug: YES X NO___

Bottom plug(in place): YES___, CALC___, NO X Dakota plug: YES X, NO___

Plugged through TUBING___, CASING___ Elevation: 1825 GL

I did[11-16-95] / did not[X] observe the plugging.

DATE 11-16-95
INV. NO. 44040

[Signature]
(agent)
Form CP-2/3