

4-050172

9-26

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-141-20,278-00-00
NE SE NW /4 SEC. 09, 10 S, 12 W
3630 feet from S section line
2970 feet from E section line

Operator license# 5184 Lease Becker well # 2

Operator: Shields Oil Producers Inc. County Osborne

Address: Shields Building Well total depth 3091 feet ^{100.45}
Russell, Kansas 67665 Conductor Pipe: inch @ feet
(913)483-3141 Surface pipe 8 5/8 inch @ 230 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Allied Cementing License#

Address:

Company to plug at: Hour: AM Day: 26 Month: September Year: 1993

Plugging proposal received from: Burton Berry

Company: Shields Oil Producers Inc. phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 900 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 675 feet " 80 " Mousehole: 10 sacks
3rd plug @ 285 feet " 40 "
4th plug @ 40 feet " 10 " with 8 5/8" wiper plug

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:00 AM, Day: 26, Month: September, Year: 1993

Actual plugging report: Hole reported plugged as above.
Order 180 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Elevation: 1804, Anhydrite: 888-919 feet, Anhydrite plug: 900
Bottom plug (in place): Yes X, Calc , No Arbuckle: NONE

10-8-93
OCT 08 1993

Did NOT penetrate Arbuckle, cemented by Allied Cementing Company CONSERVATION DIVISION
Wichita, Kansas

I did[] / did not[X] observe the plugging. Marvin Miller

Marvin L. Miller P.I.R.T.II
(agent)

INVOICED

DATE 10-8-93

INV. NO. 38915 9-26