

4 060076

3-20

11 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-141-20,249-00-00
S2 NE 10, SEC. 10, T 10 S, R 12 W/E
2970 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6176

Lease Name Single Well # 1

Operator: Lyan Holt Well Servicing

County Osborne 107.41

Name & Address W. Hwy. 40 Box 671

Well Total Depth 3305 feet

Russell, KS 67665

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 204'

Abandoned Oil Well XXXXXXXXXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347 Chase, KS

Company to plug at: Hour: 10:00AM Day: 20 Month: March Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: Order 225 sxs. 60/40 pos 8%gel and hulls.

Pull casing and plug well.

Sand back to 2940' and spot 5 sxs. cement with dump bailer. Done on 3-19-90

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXX Part _____ None _____

Operations Completed: Hour: 11:00AM Day: 20 Month: March Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" at 204' w/145 sxs. 5 1/2" at 3087' w/150 sxs.

Sanded back to 2940' and spotted 5 sxs. cement, shot off and pulled casing.

Tied onto surface pipe and pumped 225 sxs. 60/40 pos 8%gel and 500# hulls.

Max pressure 1000# SIP 600#

Remarks: Allied Cementing
(additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 13 1990

INV. NO. 278

(did) observe this plugging.

STATE CORPORATION COMMISSION
Conservation Division
Wichita, Kansas

4-18-90
Gib-S

Signed Herb Deines
(TECHNICIAN)

Herb Deines