

4-060942

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

8-7

API Number: 15-141-20,273-0001

NW NW SW /4 SEC. 10, 10 S, 12 W
2310 feet from S section line
4950 feet from E section line

Operator license# 3956

Lease Princ OWWO Well # 2

Operator: Brungardt Oil & Leasing Co.

County: Osborne 35.00

Address: P.O. Box 871
Russell, Kansas 67665

Well total depth 803 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 221 feet

Aband. oil well X, Gas well, Input well, SWD, D & A X

Plugging contractor: Shields Oil Producers License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00 A.M. Day: 7 Month: August Year: 1996

Plugging proposal received from: Burt Beery

Company: Shields Oil Producers, Inc. Phone:

Were: Order 115 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
KANSAS CORP. COM.
FEB 18 21 A 10:54

Plugging Proposal Received by: Herb Deines 8-21-96

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 12:15 P.M. Day: 7 Month: August Year: 1996

Actual plugging report: Drilled outside of original hole in 100 sack plug section. Drilled to 805'. Approximately top of anhydrite. Pulled to 615' and spotted 60 sack plug at this point. Pulled to 260' and pumped 40 sack plug. Pulled to 40' and circulated cement with 10 sxs. 15 sxs in rathole and 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [] / did not [X] observe the plugging.

[Signature]
DH (agent)

INVOICED
DATE AUG 27 1996

INV. NO. 46352

8.7 NOV 04 1996