

4- 071007

9-16

375

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-141-20,273-00-00

NW NW SW /4 SEC. 10, 10 S, 12 W
2310 feet from S section line
330 feet from E section line

Operator license# 5184 Lease Langley well # 2

Operator: Shields Oil Producers, Inc. County Osborne

Address: Shields Building Well total depth 3050 feet
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
M.L. Ratts Surface pipe 8 5/8 Inch @ 221 feet

99.12

Aband. oil well ____, Gas well ____, Input well ____, SWD ____, D & A X

Plugging contractor: Shields Drilling License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 16 Month: September Year: 92

Plugging proposal received from: Burton Berry

Company: Shields Building Phone: 913-483-3141

Were: 8 5/8" - 221' cwc. w/150 sx. 60/40 pozmix - 2% gel. - 3% c.c.
By Allied Cement. No Arbuckle - Elv. 1765' - Anhy. 803' - No circulation
problems - Mud condition 44 vis. - 9.5 wt. - 10 W.L. Proposal 200 sx.
60/40 pozmix - 6% gel. - 1 sx. flocele. Spot with drill stem, circulate
hole, heavy mud between all plugs.
25 sx. @ 810' - 100 sx. @ 615' - 40 sx. @ 270' - 10 sx. @ 40'.
15 sx. in Rathole - 10 sx. in Mousehole. (circulate)

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: P.M. Day: 16 Month: September Year: 92

Actual plugging report: Shields ordered 200 sx. 60/40 pozmix - 6% gel.
and 1 sx. flocele. Spotted with drill stem, circulated hole, heavy mud
between all plugs.
1st. plug @ 810' w/25 sx. cement.
2nd. plug @ 615' w/100 sx. cement with 1 sx. flocele.
3rd. plug @ 270' w/40 sx. cement.
4th. plug @ 40' w/10 sx. cement.
15 sx. in Rathole (cir.) 10 sx. in Mousehole (cir.)

16-2-92

RECEIVED
STATE CORPORATION COMMISSION

OCT 2 1992

Remarks: Cemented by: Allied Cementing
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X NO
Plugged through TUBING, CASING. Elevation: 1763 ft.

I did not [X] observe the plugging.

Marion J. Schmidt
(agent)

INVOICED
DATE 10-21-92
INV. NO. 36539