

4-071016

11-17

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-141-20,270-00-00

SW SW NW /4 SEC. 10, 10 S, 12 W  
2970 feet from S section line  
330 feet from W section line

Operator license# 67665 Lease Single B well # 1

Operator: Shields Oil Producers, Inc. County Osborne

Address: Shields Building Well total depth 3977 feet <sup>129.25</sup>  
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet  
Marvin Ratts Surface pipe 8 5/8 Inch @ 211 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A X <sup>KCC</sup>

Plugging contractor: Allied Cementing License#    

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 17 Month: November Year: 92

Plugging proposal received from: Marvin Ratts

Company: Shields Oil Producers, Inc. Phone: 913-483-3141

Were: 8 5/8" - 211' S.P. cwc. with 140 sx. 4 1/2" casing set @ 3148'  
w/100 sx. cement. Stage tool @ 845'cwc. w/200 sx. cement. Perf's @  
3032' - 3036'. Proposal 275 sx. 65/35 pozmix - 8% gel. and 5 sx. hulls.  
Load both 4 1/2" casing top to bottom and 4 1/2" x 8 5/8" annulus.  
Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 2:30P.M., Day: 17, Month: November, Year: 92

Actual plugging report: Shields Drilling ordered 275 sx. 65/35 pozmix -  
8% gel. and 5 sx. hulls. Pumped in with pump truck. Annulus 4 1/2" x  
8 5/8" previously squeezed with 200 sx. cement circulated with cement  
from 845'. (1) Squeezed 4 1/2" x 8 5/8" annulus with 20 sx. cement  
Max. 300 P.S.I. Shut in 300 P.S.I. (2) Pumped in 4 1/2" casing with  
15 sx. cement followed with 210 sx. cement with 5 sx. hulls added.  
Max. pressure 1200 P.S.I. Shut in pressure 1000 P.S.I.

11-23-92

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Cemented by: Allied Cement - Russell, Kansas

NOV 23 1992

Condition of casing(in hole):GOOD X BAD     Anhy.plug:YES X NO    

Bottom plug(in place):YES X, CALC    , NO     Dakota plug:YES X NO    

Plugged through TUBING    , CASING X. Elevation:     GL

I did [ X ], did not [     ] observe the plugging.

Marion J. Schmidt  
(agent)

INVOICED

DATE 12-8-92

INV. NO. 37017