

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 119-20382-0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date Spud 12-4-1979 (Original)

Well Operator: Raydon Exploration, Inc. (Owner / Company Name) KCC License #: 30604 (Operator's)

Address: 9400 N. Broadway, Ste. 400 City: Oklahoma City

State: OK Zip Code: 73114 Contact Phone: (620) 624 - 0156

Lease: Adams Ranch Well #: 1-17R Sec. 17 Twp. 34 S. R. 29 East West

SE SESW - NW Spot Location / QQQQ County: Meade

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 1532' Cemented with: N/A Sacks

Production Casing Size: 4-1/2" Set at: 6290' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: 6182'-6187'

Elevation: 2542/2547 (G.L. / K.B.) T.D.: 6295' PBDT: 6254' Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set CIBP at 6150', dump 25 sx cement on plug, shoot off casing at ±4000', pull to 1560', pump 50 sx, pull to 500', pump 40 sx, pull to 40', pump 20 sx, 60/40 poz, 6% Gel

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David Rice, Crown Consulting, Inc.

Phone: (620) 624 - 0156

Address: PO Box 1816 City / State: Liberal, KS 67905-1816

Plugging Contractor: Sargent-Lillard (Company Name) KCC License #: 32833

Address: P.O. Box 1450, Woodward, OK 73802 (Contractor's) Phone: (580) 254 - 1881

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9-27-06 Authorized Operator / Agent: David E Rice (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**RECEIVED
SEP 29 2006
KCC WICHITA**

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Raydon Exploration, Inc.
9400 N. Broadway #400
Oklahoma City, OK 73114

October 10, 2006

Re: ADAMS RANCH #1-17R
API 15-119-20382-00-01
SESWNW 17-34S-29W, 2310 FNL 990 FWL
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



Barry Metz
Deputy Director

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888