

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

RECEIVED
MAR 16 2006
KCC WICHITA

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-129 45429-20008-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Nadel and Gussman, L.L.C. KCC LICENSE # 32638
(owner/company name) (operator's)

ADDRESS 3200 First Place Tower CITY Tulsa

STATE Oklahoma ZIP CODE 74103 CONTACT PHONE # (918) 5833333

LEASE Williams WELL# 1-34 SEC. 34 T. 31S R. 42 (East/West)

C - SE - NW - NW SPOT LOCATION/QQQQ COUNTY Morton

990 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE NA SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8 SET AT 1425 CEMENTED WITH UKN TOC - Surf SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 3241 CEMENTED WITH 275 sx SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2831-39; 3013-23; 3083-89; 2778-84; 2786-96

ELEVATION 3482 GL T.D. 1150320 P.B.T.D. 51503204 ANHYDRITE DEPTH +/-900'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ +/-2750', cap with 10-15 sx cement. Set cement plug @ 1375-1475; set cment plug @ +/-800-900'. Cement plug @ +/-1--30'. Cut off 4-5' below GL and weld cap on csg.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

John May PHONE# (620) 697-2137

ADDRESS P.O. Box 773 City/State Elkhart, KS 67950

PLUGGING CONTRACTOR Sargent & Horton Plugging, Inc. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS Rt. 1, Box 49BA, Tyrone, OK 73951-9731 PHONE # (580) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/10/06 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Nadel and Gussman, LLC
15 E. 5th, Suite 3200
Tulsa, OK 74103-4313

October 10, 2006

Re: WILLIAMS #1-34
API 15-129-20008-00-01
SENWNW 34-31S-42W, 990 FNL 990 FWL
MORTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



Barry Metz
Deputy Director