

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 041-20,045-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: Bruce Oil Company KCC License #: 5610
(Owner / Company Name) (Operator's)

Address: 1704 Limestone Road City: McPherson

State: Kansas Zip Code: 67460 Contact Phone: (620) 241-2938

Lease: Riordan Well #: 3 Sec. 6 Twp. 15 S. R. 1 East West

C - SW - SE - SW Spot Location / QQQQ County: Dickinson

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 112 Cemented with: 125 Sacks

Production Casing Size: 4 1/2 Set at: 2635 Cemented with: 180 Sacks

List (ALL) Perforations and Bridgeplug Sets: perfs 2595-2600, mudded off bottom when got hole in pipe at 2140', squeezed with 100 sax cement, lost hole, outside pipe at 2147'

Elevation: n/a (G.L. / K.B.) T.D.: 2636 PBTD: _____ Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand off bottom to 50 feet above open hole or perforations, put 4 sax cement on sand, rip off and pull casing, set bridge plug at 250 feet, fill hole to surface with cement slurry.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lonny Bruce, Operating Manager
Phone: (620) 241-2938

Address: 406 Ponderosa Ct. City / State: McPherson, Kansas 67460

Plugging Contractor: Sunflower Well Service KCC License #: 30280
(Company Name) (Contractor's)

Address: P.O. Box 341, Canton, Kansas 67428 Phone: (620) 628-4723

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10/5/06 Authorized Operator / Agent: Lonny Bruce (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT - 6 2006
KCC WICHITA

BM&S OIL
 BOX 316
 CANTON, KS 67428
 CONTR KS DRLG & WELL SVC CTY DICKINSON
 GEOL HARRY HOPKINS FIELD ASH GROVE
 E NA _____ CM 9/13/80 CARD ISSUED 1/22/81 IP P 18 BO & 90 BWPD
 API 15-041-20,045 MISS 2595-2600

#3 RIORDAN 6-15-1E SW SE SW

+	+
+	+
+	+

DL	TOPS	DEPTH	DATUM
LANS		1952	
KC		2194	
MISS CHT		2587	
MISS LM		2627	
RTD		2636	

8-5/8" 112/125sx, 4 1/2" 2635/180sx
 NO DSTS
 MICT - CO, PF (MISS) 5/2595-2600, AC
 300 G (7 1/2%), SWB LD W/SO, POP, P 18
 BO & 90 BWPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 OCT - 6 2003
 KCC WICHITA

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bruce Oil Company, L.L.C.
1704 Limestone Rd.
McPherson, KS 67460

October 10, 2006

Re: RIORDAN #3
API 15-041-20045-00-00
SWSESW 6-15S-1E, 330 FSL 1650 FWL
DICKINSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely



Barry Metz
Deputy Director