

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-041-00070-00-02 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 2-11-55.

Well Operator: Bruce Oil Company KCC License #: 5610
(Owner/Company Name) (Operator's)

Address: 1704 Limestone Road City: McPherson

State: Kansas Zip Code: 67460 Contact Phone: (620) 241-2938

Lease: Riordan Well #: 1 Sec. 6 Twp. 15 S. R. 1 East West

C - SE - SE - SW Spot Location / QQQQ County: Dickinson

308 330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

305 72310 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 100 Cemented with: unknown Sacks

Production Casing Size: 4 1/2 Set at: 2590 Cemented with: unknown Sacks

List (ALL) Perforations and Bridgeplug Sets: open hole to 2602'

Elevation: 1319 (G.L. / K.B.) T.D.: 2602 PBTD: _____ Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand off bottom to 50 feet above open hole or perforations, put 4 sax cement on sand, rip off and pull casing, set bridge plug at 250 feet, fill hole to surface with cement slurry.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? prior to existence

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lonny Bruce, Operating Manager

Phone: (620) 241-2938

Address: 406 Ponderosa Ct. City / State: McPherson, Kansas 67460

Plugging Contractor: Sunflower Well Service KCC License #: 30280

Address: P.O. Box 341, Canton, Kansas 67428 Phone: (620) 628-4723
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-116) will be guaranteed by Operator or Agent

Date: 10/5/06 Authorized Operator / Agent: Lonny Bruce (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT - 6 2006
KCC WICHITA

DONALD T INGLING #1 RIORDAN 6-15-1E SE SE SW

Contr. _____ DICKINSON County


E 1319 Comm. _____ Comp. 2-11-55 IP 5/4 BOPD
PHY POT

Tops	Depth	Datum
LANS	1916	-627
BURG SND	2583	-1261
MISS	2588	-1269
TD	2602	-1283

Casing
 8" 100
 4" 2590

CO 2602: ACID 550: 3 BOPH

ASH GROVE POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
OCT -8 1955
KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bruce Oil Company, L.L.C.
1704 Limestone Rd.
McPherson, KS 67460

October 10, 2006

Re: RIORDAN #1
API 15-041-00070-00-02
SESESW 6-15S-1E, 308 FSL 3037 FEL
DICKINSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



Barry Metz
Deputy Director

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000