

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-10127-0000

LEASE NAME PANOMA

WELL NUMBER 1-12

^{POST} 2440' FNL Ft. from S Section Line

s w s w n e 2440' EWL Ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to GORS. Div.
office within 30 days

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

SEC. 12 TWP. 31S RGE. 38W (E) or (W)

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

COUNTY STEVENS

PHONE # 072) 444-9001 OPERATORS LICENSE NO. 4824

Date Well Completed 1954

Character of Well GAS

Plugging Commenced 10/06/06

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 10/06/06

The plugging proposal was approved on 08/22/06 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 3120' Bottom 2670' T.D. 2670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2433'	2670'	10 3/4"	526'	0'
				7"	2430'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

10/06/06 Witnessed by K Jehlik, KCC. Tag CIBP @2350'. NU cmtr to 7" csg, pmp 10 sx cmt 2350'-2300'. Pmp 24 bbl mud 2300' - 1710'. Pmp 40 sx cmt frm 1710'-1510' & 38 bbl mud to 560'. Pmp 40 sx cmt plug frm 560' - 360'. Pmp 13 bbl mud to 40' & 8 sx cmt 40'- 0'. Cut 7 csg & 10 3/4" surf csg @ 3' bgl, weld on trash cover - ID plate.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


RECEIVED

OCT 13 2006

KCC WICHITA

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



ANGIE G. HERNANDEZ AND SWORN TO before me this 11th day of October, 2006

Notary Public, State of Texas
My Commission Expires JULY 14, 2009
Expires: 7/14/2009 Notary Public

Handwritten initials