

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Indian Oil Co., Inc.
Address: P.O. Box 209 Medicine Lodge, Ks. 67104
Phone: (620) 886 3763 Operator License #: 31938

API Number: 15 - 097-20,534 - 00-00
Lease Name: Fisher
Well Number: 1

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): C - NE - SW
1980 Feet from _____ North / South Section Line
1980 Feet from East / West Section Line

The plugging proposal was approved on: _____ (Date)
by: Eric Maclaren (KCC District Agent's Name)

Sec. 2 Twp. 27 S. R. 17 East West
County: Kiowa

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Date Well Completed: 1979
Plugging Commenced: 9-16-06
Plugging Completed: 9-18-06 *per PCP/13*

*KCC
PKT
10-16-06
per
COPS
PKT*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	From	To	Size	Put In / Pulled Out
				8-5/8"	393' / None
				4-1/2"	4709' / 2243' 2234'
					<i>KCC PKT 10/16/06 per COPS</i>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4540' and 4 sacks cement. Cut casing loose 2243', pulled up to 1000', purped 15 sxs. gel & 50 sxs. cement, pulled up to 420', purped 50 sxs. cement, pulled up to 40' and circulated 35 sxs. cement to surface, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524


Name of Party Responsible for Plugging Fees: Indian Oil Company, Inc.
State of Kansas County: Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Mike Kelso*
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 11th day of October, 20 06

Irene Herzberg My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 13 2006
KCC WICHITA

PKT