

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Eagle River Energy Corporation
Address: 7060 S. Yale, Suite 609
Phone: (918) 494-8928 Operator License #: 31070
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: May 1, 2006 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing-Kansas City Depth to Top: 3006 Bottom: 3320 T.D. 3356

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-19055-00-00
Lease Name: Kowalsky
Well Number: 4
Spot Location (QQQQ): _____ - SE - SE - SW
330 313 Feet from North / South Section Line
2310 3080 Feet from East / West Section Line
Sec. 6 Twp. 19 S. R. 10 East West
County: Rice
Date Well Completed: 10/60
Plugging Commenced: 10/03/06
Plugging Completed: 10/03/06

KCC
10/17/06
Per
GPS
Figs

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing-Kansas City	oil, water	3022	3241	8 5/8; 5 1/2	256'; 3353'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran in hole to 2400' w/2" tbg. Spot 70 sx 60/40 10% cement w/6 sx c/s hulls. Move up to 1300' spot w/35 sx cement.
Move to 900' spot 35 sx. Move up to 300' circulate cement top and through backside between 8 5/8 and 5 1/2.

Name of Plugging Contractor: Classic Well Service License #: 32098
Address: P.O. Box 539, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Eagle River Energy Corporation
State of Oklahoma County, Tulsa, ss.

Mark P. Godsey (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark P. Godsey
(Address) 7060 S. Yale, Suite 609, Tulsa, OK 74136

SUBSCRIBED and SWORN TO before me this 11th day of October 20 06
Jana Bravette My Commission Expires: 11-25-08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 16 2006
KCC WICHITA