

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-141-20,270-00-00

LEASE NAME Single "B"

WELL NUMBER 1

2,970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 10 TWP. 10 RGE. 12 ~~(E)~~ or (W)

COUNTY Osborne

Date Well Completed 9-3-92

Plugging Commenced 11-17-92

Plugging Completed 11-17-92

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., Russell, KS. 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-17-92 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,057'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	211'	Cmtd. w/140 sax
				4 1/2"	3,148'	Cmtd. w/300 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Pump 15 sax cement followed with 210 sax 60-40 Pozmix w/8% jel and 5 sax hulls down 4 1/2" casing. Maximum pressure 1200#, shut in pressure 1000#. Pump 20 sax cement down 8 5/8" annulus. Maximum pressure 300#, shut in pressure 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Oil Producers, Inc. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman

(Employee of Operator Shields Oil Producers, Inc. of Wichita, Kansas)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. - Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 92

Ruth Phillips

Notary Public

My Commission Expires: \_\_\_\_\_



RECEIVED  
STATE CORPORATION COMMISSION  
DEC 8 1992  
12-8-92  
Wichita, Kansas