

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-141-203310000

LEASE NAME Becker

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
990 Ft. from ^N Section Line
1,650 Ft. from E Section Line

SEC. 9 TWP. 10 RGE. 12 (E) or (W)

COUNTY Osborne

Date Well Completed 3-24-97

Plugging Commenced 3-24-97

Plugging Completed 3-31-97
3-25-97

LEASE OPERATOR Brungardt Oil & Leasing Co.

ADDRESS PO Box 871, Russell, KS. 67665

PHONE/(913) 483-4975 OPERATORS LICENSE NO. 3956

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-24-97 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,095'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	208'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Push bridge plug to 880', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 625', pump 80 sax cement on plug thru drill pipe. Push bridge plug to 260', pump 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brungardt Oil & Leasing Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman

Contractor

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack P. Beeman


(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 8th day of April, 1997

Rush Phillips
Notary Public

My Commission Expires: _____





Shields


WELL LOG

15-141-20331-00-00

Russell, Kansas

Operator: Shields Oil Producers, Inc.
 Well: Becker #1
 Commenced: March 24, 1997
 Completed: March 31, 1997
 Contractor: Shields Drilling Co.

Well Description: SE NW NE
 Sec. 9-10S-12W
 Osborne Co., Kansas



Elevation: 1,804' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	208'	Cmtd. w/150 sax

..... Figures Indicate Bottom of Formations

Shale & snad	860'	
Anhydrite	895'	
Shale	1,990'	
Shale & lime	2,310'	
Shale	2,485'	
Shale & lime	3,045'	
Lime	3,095'	RTD

RECEIVED
 KANSAS CORP COMM
 1997 APR 10 A 10:13

Notes