

API NUMBER 15-141-203090000

LEASE NAME Becker

WELL NUMBER 1

330 Ft. from <sup>N</sup> Section Line

1,220 Ft. from E Section Line

SEC. 9 TWP. 10 RGE. 12 (E) or (W)

COUNTY Osborne

Date Well Completed 11-2-95

Plugging Commenced 11-2-95

Plugging Completed 11-2-95

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR ESP Development, Inc.

ADDRESS 17746 177th Blvd., Paradise, KS. 67658

PHONE#(913) 998-4413 OPERATORS LICENSE NO. 6194

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-2-95 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3,192'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	208'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Push bridge plug to 900', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 625', pump 80 sax cement on plug thru drill pipe. Push bridge plug to 260', pump 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 10 sax cement down mouse hole and 15 sax cement down rat hole.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co.

Address PO Box 709, Shields Bldg., Russell, KS. 67665

License No. 5184  
 RECEIVED  
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ESP Development, Inc.

STATE OF KANSAS COUNTY OF RUSSELL

NOV 14 1995  
 11-14-95  
 RECEIVED  
 STATE CORPORATION COMMISSION

Jack P. Beeman, Sec.-Treas. (Employee of Operator or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack P. Beeman, Sec.-Treas.

(Address) PO Box 709 Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 13th day of November, 19 95

Ruth Phillips  
 Notary Public

My Commission Expires:





# Shields


## WELL LOG

15-141-20309-00-00.

Russell, Kansas

Operator: ESP Development, Inc.  
 Well: Becker #1  
 Commenced: October 27, 1995  
 Completed: November 2, 1995  
 Contractor: Shields Drilling Co.

Well Description: N/2 N/2 NE  
 Sec. 9-10S-12W  
 Osborne Co., Kansas



Elevation: 1,830' KB

Treatment:

Production: D & A

Tops:

### CASING RECORD

Size	Run	Pulled
8 5/8"	208'	Cmtd. w/140 sax

..... Figures Indicate Bottom of Formations .....

Shale	211'	
Shale & sand	895'	
Anhydrite	925'	
Shale	1,485'	
Shale & lime	1,953'	
Shale	2,130'	
Shale & lime	2,980'	
Lime	3,192'	RTD

RECEIVED  
STATE CORPORATION COMMISSION

NOV 14 1995

CONSULTING ENGINEERS  
WICHITA KANSAS

Notes