

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-141-20,277-00-00

LEASE NAME Becker

WELL NUMBER 1

990 Ft. from <sup>N</sup> ~~X~~ Section Line

2,310 Ft. from E Section Line

SEC. 9 TWP. 10 RGE. 12 ~~XX~~ or (W)

COUNTY Osborne

Date Well Completed 5-8-93

Plugging Commenced 5-9-93

Plugging Completed 5-9-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., Russell, KS. 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-5-93 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,084'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	217'	Cmt'd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Fill hole w/heavy mud. Push bridge plug to 875', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 635', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 270', spot 40 sax on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160 5184 NR KCC

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Operator) or ~~operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. - Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 26th day of May, 19 93

Ruth Phillips  
Notary

My Commission Expires:



RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1993  
5-27-93  
CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-4  
Revised 05-88