

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-141-20,271-00-00

LEASE NAME John Wallace

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 9 TWP. 10 RGE. 12 ~~XX~~or(W)

COUNTY Osborne

LEASE OPERATOR Leroy E. Tobias

ADDRESS HC 69, Box 42, Bunker Hill, Kansas 67626

PHONE#(913) 483-4565 OPERATORS LICENSE NO. 3345

Date Well Completed 8-30-92

Character of Well D & A

Plugging Commenced 8-30-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-30-92

The plugging proposal was approved on 8-30-92 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,042'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	216'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Push bridge plug to 800', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 590', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 270', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

5184 kcc

Name of Plugging Contractor Shields Drilling Co.

License No. RECEIVED
STATE CORPORATION COMMISSION

Address Shields Bldg., Russell, Kansas 67665

9-15-92

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Leroy E. Tobias

SEP 15 1992

STATE OF KANSAS COUNTY OF RUSSELL, ss.

CONSERVATION DIVISION
Wichita, Kansas

Jack P. Beeman

(Employee of ~~Operator~~ or (~~Operator~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman


(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 92

Ruth Phillips

Notary Public

My Commission Expires: _____





Shields


15-141-20271-00-00

Russell, Kansas

WELL LOG

Operator: Leroy E. Tobias
 Well: John Wallace #1
 Commenced: August 24, 1992
 Completed: August 30, 1992
 Contractor: Shields Drilling Co.

Well Description: NE SE SE
 Sec. 9-10S-12W
 Osborne Co., Kansas



Elevation: 1,742' KB
 Treatment:
 Production: D & A
 Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	216'	Cmtd. w/140 sax

..... Figures Indicate Bottom of Formations

Surface clay & shale	219'	
Shale & sand streaks	438'	
Shale & sand	789'	
Anhydrite	821'	
Shale	1,350'	
Shale & lime	2,942'	
Lime	3,042'	RTD

Notes

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1992

CONSERVATION DIVISION
Wichita, Kansas