

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-141-20,259-00-00

LEASE NAME Robinson

WELL NUMBER 1

4,950 Ft. from S Section Line

2,310 Ft. from E Section Line

SEC. 14 TWP. 10 RGE. 12 XEYor(W)

COUNTY Osborne

Date Well Completed 2-19-91

Plugging Commenced 2-19-91

Plugging Completed 2-19-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., Russell, KS. 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-19-91 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3,280'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	211'	Cmtd. w/ 25 sax

38-91
 RECEIVED

MAR - 8 1991

CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Fill hole w/heavy mud. Push bridge plug to 760', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 600', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 230', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 6th day of March, 19 91

Ruth Phillips
 Notary Public

My Commission Expires:

